BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
DTS COPY

NAME OF THE WORK: Removal of debris & dislting of drains in Dasarahlli in ward no. 15 Dasarahalli sub division

Sl. No	Description of work	Unit	Qty	Rate to be Quoted	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Removing B.S. slab of drain and stacking with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work..(PWD SR 2016-17, Page No.25, Item No. 5.32)	**Sqm**	5292.00		
2	Excavation and removal of silt and silt mix with sand in slushy condition form canal bed including disposing of the same in spoil bank or on canal embankment in layers as directed etc., complete with an initial lead upto 50m (MISR Page No.118, Item No. 51)	Cum	1274.40		
3	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Page No. 25/ Item No.5.33/ PWD SR 2016-17	Sqm	5292.00		
4	J.C.B. Excavator on hire basis including JCB Operator with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work (PWD SR 2015-16, P-XXXXVI, It.No.23)	Days	12.00		
5	Tractor 40 HP on hire basis including Tractor Driver with Helper to carryout the works on emergency as per the direction of Engineer-in-charge of the work (PWD SR 2015-16, P-XXXXVI, It.No.19)	Days	48.00		

Number of Corrections:

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

DTS Approved

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು